



Aircrete infill produced from Vertical Wall Panel off cut on site, bedded on element mortar

Insulated box lintel

Vertical Wall Panel cut on site to suit lintel.

Lintel bearing, bedded on traditional mortar

Reduced height vertical wall Panel to underside of opening

02.	23/6/17.	Ref. to DPC under lintel removed	MAB.
01.	2/3/17.	Minor mod.	MAB.
REV.	DATE.	DESCRIPTION.	BY.

These details have been produced for guidance only. It is the responsibility of the building designer to ensure that the details shown are compatible with the overall building design and will satisfy the relevant parts of the Building Regulations applicable before they are adopted into the project design.



H+H UK Limited
 Technical Services Dept.
 Celcon House
 Ightham, Sevenoaks
 Kent, TN15 9HZ.
 Tel +44 (0)1732 880580
 E-mail tsd@hhcelcon.co.uk

TITLE
**Vertical Wall Panel
 loadbearing lintel installation**

DWG No. **VED003**

DRAWN BY **MAB** CHECKED BY **SJK**

DATE **21/7/15** SCALE **NTS** REV.NO. **02**